

Alternatives Public Meeting Canoe Creek Road

Project Development and Environment (PD&E) Study

From Deer Run Road to US 192

Osceola County, FL

Financial Project Identification (FPID) Number: 449217-1


Tuesday, July 18, 2023

About the Public Meeting

This public meeting is being conducted in a hybrid format:

- In-Person
- Virtual
- Dial-in

Dial-in attendees are in "listen-only" mode. A copy of the presentation is available at: www.osceola.org/go/canoecreekroad





Title VI Compliance



Osceola County complies with various non-discrimination laws and regulations, including Title VI of the Civil Rights Act of 1964 and the Americans with Disabilities Act (ADA).

Public participation is solicited without regard to race, color, national origin, age, sex, religion, disability, or family status.

For questions or concerns, you may contact :

Osceola County *Title VI Coordinator* **Brenda Hernandez** 700 Generation Point Kissimmee, FL 34744 (407) 742-1208 TTY: 711 (Florida Relay System) *Brendai.Hernandez@Osceola.org*

"No person shall, on the grounds of race, color, or national origin, be excluded from participation in, be denied the benefits of, or be subjected to discrimination under any program or activity receiving federal assistance." —Civil Rights Act of 1964

Study Compliance






Florida Department of Transportation

The environmental review, consultation, and other actions required by applicable federal environmental laws for this project are being, or have been, carried out by the Florida Department of transportation (FDOT) pursuant to 23 U.S.C. § 327 and a Memorandum of Understanding dated May 26, 2022, and executed by the Federal Highway Administration and the FDOT.

Project Development Process



OSCEOLA

Y be first to what's next.

Study Overview





- Project Limits:
 - Deer Run Road to US 192
 - Approximately 4.65 miles
- Evaluates widening the existing twolane road to a four-lane divided roadway
- Evaluates enhancing pedestrian and bicycle features
 - Current project limits contain a discontinuous sidewalk
 - Proposed improvements include a continuous sidewalk and shared use path
- Evaluates intersection operations

Purpose and Need



- What is the purpose of the project?
 - Improve traffic mobility
 - Add capacity
 - Provide intersection and operational improvements
 - Improve bicycle and pedestrian facilities
- Why is the project needed?
 - Improve traffic operations
 - Improve safety



Existing Traffic Analysis





• Segments:

- Deer Run Road to 17th Street experiences light congestion
- 17th Street to US 192 experiences moderate congestion (northbound)

• Intersections with Canoe Creek Road:

- Old Canoe Creek Road, Nolte Road, and 17th Street experience moderate congestion
- Deer Run Road and US 192 experience heavy congestion

Crash History






- Crash Data collected 2017-2021
 - 550 recorded crashes
- Crash clusters at the following intersections (56% of all crashes):
 - Old Canoe Creek Road (92 crashes)
 - Nolte Road (108 crashes)
 - US 192 (106 crashes)
- 2 Fatalities
- 49% of crashes were rear end crashes


Existing Conditions





Existing Conditions





Canoe Creek Road PD&E Study FPID Number 449217-1

Existing Conditions






- Signalized Intersections:
 - Deer Run Road / Friars Cove Road
 - Old Canoe Creek Road / Pine Tree Drive
 - Nolte Road
 - 17th Street
 - US 192
- Transmission Poles (owned by Orlando Utilities Commission)
 - East of Canoe Creek Road from Deer Run Road to just south of Old Canoe Creek Road
 - West of Canoe Creek Road from just south of Old Canoe Creek Road to 17th Street
- Speed Limit
 - Deer Run Road to Whaley's Creek Boulevard 45-55 mph
 - Whaley's Creek Boulevard to Pine Street 45 mph
 - Pine Street to US 192 35 mph

No-Build Alternative

- No improvements would be made
- Traffic operations and mobility will degrade
- Congestion will intensify
- Current bicycle and pedestrian facilities would not be improved
- Does not meet the project's purpose and need
- Viable option throughout the duration of the study





No-Build Traffic Analysis





- Traffic is projected to the year 2050
- Traffic is projected to more than double
- Unacceptable congestion projected for majority of corridor
- All signalized intersections will fail
- 24 out of the 26 unsignalized intersections will fail


Proposed Typical Section





Proposed Typical Section





Access Management






• Existing:

- Two-lane undivided non-restrictive
 - No median openings
- Proposed:
 - Four-lane divided restrictive
 - Directional median openings spaced 660 feet
 - Full median openings or signals spaced 1,320 feet
 - Addition of 3 signals:
 - Portofino Vista Boulevard
 - Creek Woods Drive
 - Settlers Trail


Old Canoe Creek Alternatives





Nolte Road Alternatives





Evaluation Matrix - Intersections

	Old Canoe Cre	ek Road Intersectio	on Alternatives	Nolte Road Intersection Alternatives			
	Signalized Intersection	Displaced Left Turn	No-Build	Signalized Intersection	Displaced Left Turn	No-Build	
Total Parcels Impacted	59	66	0	44	57	0	
Total Acres Impacted	3.0	4.7	0	4.6	6.4	0	
Total Relocations	3	10	0	2	7	0	
Potential NRHP ¹ -eligible Impacts	0	0	0	0	0	0	
Utility Impacts	Moderate	High	None	Moderate	High	None	
Wetland and Surface Water Impacts (acres)	0.2	0.2	0	0.9	0.9	0	
Floodplain Impacts (acres)	2.8	2.8	0	4.0	4.0	0	
Contamination Sites	6	6	6	1	1	1	
Estimated Construction Cost (\$ million)	\$17.3	\$19.0	\$0	\$21.9	\$23.9	\$0	

¹National Register of Historic Places



Evaluation Matrix - Intersections



		Run Road to Pine ernatives	Segment 2: Pine Street to US 192 Alternatives				
	Build	No-Build	Hold West	Hold East	No-Build		
Total Parcels Impacted	100	0	46	46	0		
Total Acres Impacted	17.1	0	2.4	2.4	0		
Total Relocations	4	0	27	25	0		
Potential NRHP ¹ -eligible Impacts	0	0	0	0	0		
Utility Impacts	Minor	None	Minor	Minor	None		
Wetland and Surface Water Impacts (acres)	1.6	0	0.0	0.0	0		
Floodplain Impacts (acres)	3.6	0	0.0	0.0	0		
Contamination Sites	7	7	3	3	3		
Estimated Construction Cost (\$ million)	\$63.2	\$0	\$10.5	\$10.5	\$0		

¹National Register of Historic Places

Right of Way Acquisition




- Final Right of Way will be determined during the Design Phase
- Right of way phase is not currently funded
- For questions about the right of way process, contact the Project Manager, Stephanie Underwood at <u>Stephanie.Underwood@Osceola.org</u>



Stay Informed





Your input matters



- In-Person:
 - Submit a comment form
- Virtually:
 - GoToWebinar: Type your question/comment in the Question box
- By US Mail to the Project Manager
- Email the Project Manager

Please submit your comments and questions by July 28, 2023



Project Website www.osceola.org/go/canoecreekroad

Project Manager Contact Information

Stephanie Underwood, P.E.



Osceola County Project Manager Department of Transit and Transportation 1 Courthouse Square, Suite 3100

Kissimmee, FL 34741

Stephanie.Underwood@Osceola.org

Study Schedule



Tentative – Subject to change

Project Milestones	2022		2023				2024			
	April June	July September	October December	January March	April June	July September	October December	January March	April June	July September
Begin Study	\star									
Data Collection										
Traffic Forecasting and Analysis							Tonight's Alternatives Public Meeting			
Develop Improvement Alternatives										
Conduct Alternatives Open House						\star				
Select and Refine Preferred Alternative										
Prepare Documents										
Conduct Public Hearing									*	
Project Approval										\star
Stakeholder Engagement										

(407) 742-0565

Thank you for participating

Please submit comments and questions to Stephanie Underwood by **July 28, 2023**

Stephanie.Underwood@Osceola.org

1 Courthouse Square, Suite 3100 Kissimmee, FL 34741

www.osceola.org/go/canoecreekroad





